



# Bulk Asbestos Analysis

By Polarized Light Microscopy  
 EPA Method: 600/R-93/116 and  
 40 CFR, Part 763, Subpart E, App.E



**Customer:** JTL Services  
 3999 Sanderosa Rd.  
 Fayetteville, NC 28312

**Attn:** Jay Leonard

**Lab Order ID:** 10075503

**Analysis:** PLM

**Date Received:** 02/21/2025

**Date Reported:** 02/21/2025

**Project:** COF - ECD - 0437-23-4562 308 Currie Street  
 Fayetteville, NC 28301

Sample ID	Description	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes
Lab Sample ID	Lab Notes				Treatment
1	Ceiling Surfacing	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0001					Crushed
2	Ceiling Surfacing	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0002					Crushed
3	Ceiling Surfacing	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0003					Crushed
4	Ceiling Surfacing	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0004					Crushed
5	Ceiling Surfacing	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0005					Crushed
6	Ceiling Surfacing	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0006					Crushed
7 - A	Flooring vinyl	None Detected	20% Cellulose	80% Other	Gray Fibrous Homogeneous
10075503_0007	flooring vinyl				Teased, Dissolved
7 - B	Flooring vinyl	None Detected		100% Other	Yellow Non-Fibrous Homogeneous
10075503_0015	mastic				Dissolved

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommend that analysis of floor tiles, vermiculite, and/or heterogenous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Analytical uncertainty available upon request. Scientific Analytical Institute participates in the NVLAP Proficiency Testing program. Unless otherwise noted blank sample correction was not performed. Estimated MDL is 0.1%.

Charmel Dozier (16)

Analyst

Approved Signatory



# Bulk Asbestos Analysis

By Polarized Light Microscopy  
EPA Method: 600/R-93/116 and  
40 CFR, Part 763, Subpart E, App.E



**Customer:** JTL Services  
3999 Sanderosa Rd.  
Fayetteville, NC 28312

**Attn:** Jay Leonard

**Lab Order ID:** 10075503

**Analysis:** PLM

**Date Received:** 02/21/2025

**Date Reported:** 02/21/2025

**Project:** COF - ECD - 0437-23-4562 308 Currie Street  
Fayetteville, NC 28301

Sample ID	Description	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes
Lab Sample ID	Lab Notes				Treatment
8	Flooring vinyl	None Detected	10% Fiber Glass	90% Other	Beige, Green Fibrous Homogeneous
10075503_0008	flooring vinyl only, no mastic				Teased, Dissolved
9 - A	Flooring vinyl	None Detected	20% Cellulose	80% Other	White Fibrous Homogeneous
10075503_0009	flooring vinyl				Teased, Dissolved
9 - B	Flooring vinyl	None Detected		100% Other	Yellow Non-Fibrous Homogeneous
10075503_0016	mastic				Dissolved
10	Joint Compound	None Detected	10% Cellulose	90% Other	Tan, White Fibrous Homogeneous
10075503_0010	sheetrock with paint only				Crushed
11	Joint Compound	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0011					Crushed
12	Joint Compound	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0012					Crushed
13	Joint Compound	None Detected		100% Other	White Non-Fibrous Homogeneous
10075503_0013					Crushed
14	Shingles	None Detected	15% Fiber Glass	85% Other	Black Fibrous Homogeneous
10075503_0014					Dissolved

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommend that analysis of floor tiles, vermiculite, and/or heterogenous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Analytical uncertainty available upon request. Scientific Analytical Institute participates in the NVLAP Proficiency Testing program. Unless otherwise noted blank sample correction was not performed. Estimated MDL is 0.1%.

Charmel Dozier (16)

Analyst

Approved Signatory

10075503.

**Client:** JTL services LLC  
**Contact:** John Leonard  
**Address:** 3999 Sanderosa Road  
**Phone:** Fayetteville NC 28312  
**Fax:** 910-237-3519  
**Email:** moldservicesjtl@aol.com  
  
**Project:** COF - ECD - 0437-23-4562  
 308 Currie Street  
**Client Notes:** Fayetteville, NC 28301  
  
**P.O. #:**  
**Date Submitted:** 2/18/2025 0:00  
  
**Analysis:** PLM  
**TurnAroundTime:** 12

**\*Instructions:**  
 Use Column "B" for your contact info  
  
 To See an Example Click the  
 bottom Example Tab.  
  
 Enter samples between "<<" and ">>"  
 Begin Samples with a "<<" above the first sample  
 and end with a ">>" below the last sample.  
 Only Enter your data on the first sheet "Sheet1"  
  
 Note: Data 1 and Data 2 are optional  
 fields that do not show up on the official  
 report, however they will be included  
 in the electronic data returned to you  
 to facilitate your reintegration of the report data.

**Scientific Analytical Institute**  
  
**4604 Dundas Drive**  
**Greensboro, NC 27407**  
**Phone: 336.292.3888**  
**Fax: 336.292.3313**  
**Email: lab@sailab.com**

Sample Number	Data 1	Sample Description	Data 2
<<			
1	Living Room Ceiling Surfacing	Ceiling Surfacing	
2	Bedroom Ceiling Surfacing	Ceiling Surfacing	Right Side
3	Kitchen Ceiling Surfacing	Ceiling Surfacing	
4	Bedroom Ceiling Surfacing	Ceiling Surfacing	Left side
5	Bathroom ceiling Surfacing	Ceiling Surfacing	
6	Bedroom Ceiling Surfacing	Ceiling Surfacing	Front left side
7	Kitchen Flooring	Flooring vinyl	
8	Hallway Flooring	Flooring vinyl	
9	Bathroom Flooring	Flooring vinyl	
10	Living Room wall Joint Compound	Joint Compound	
11	Bedroom Wall Joint Compound	Joint Compound	Left Side
12	Hallway Wall Joint Compound	Joint Compound	
13	Kitchen Wall Joint Compound	Joint Compound	
14	Roofing Shingles	Shingles	
>>			

Accepted   
 Rejected

Relinquished By \_\_\_\_\_

Received By CS 2/21 10 AM



Company Contact Information	
Company: JTL Services LLC	Contact: Jay Leonard
Address: 3999 Sandevosa Road	Phone <input checked="" type="checkbox"/> : 910-237-3519
Fayetteville, NC 28312	Fax <input type="checkbox"/> :
	Email <input checked="" type="checkbox"/> : moldservicesjtl@aol.com

Asbestos Test Types	
PLM EPA 600/R-93/116 (PLM)	<input checked="" type="checkbox"/>
Positive stop	<input type="checkbox"/>
PLM Point Count 400 (PT4)	<input type="checkbox"/>
PLM Point Count 1000 (PTM)	<input type="checkbox"/>
PCM NIOSH 7400-A Rules (PCM)	<input type="checkbox"/>
B Rules (PCB) <input type="checkbox"/> TWA (PTA) <input type="checkbox"/>	
TEM AHERA (AHE)	<input type="checkbox"/>
TEM Level II (LII)	<input type="checkbox"/>
TEM NIOSH 7402 (TNI)	<input type="checkbox"/>
TEM Bulk Qualitative (TBL)	<input type="checkbox"/>
TEM Bulk Chatfield (TBS)	<input type="checkbox"/>
TEM Bulk Quantitative (TBQ)	<input type="checkbox"/>
TEM Wipe ASTM D6480-05	<input type="checkbox"/>
TEM Microvac ASTM D5755-02	<input type="checkbox"/>
TEM Water EPA 100.2 (TW1)	<input type="checkbox"/>
Other: _____	<input type="checkbox"/>

Billing/Invoice Information	Turn Around Times	
Company: Credit Card on File	90 Min. <input type="checkbox"/>	48 Hours <input type="checkbox"/>
Contact: COF-ECD	3 Hours <input type="checkbox"/>	72 Hours <input type="checkbox"/>
Address: 308 Currie Street	6 Hours <input type="checkbox"/>	96 Hours <input type="checkbox"/>
Fayetteville NC	12 Hours <input checked="" type="checkbox"/>	120 Hours <input type="checkbox"/>
28301	24 Hours <input type="checkbox"/>	144+ Hours <input type="checkbox"/>

PO Number: 0437-23-4562
Project Name/Number:

Sample ID #		Volume/Area	Comments
1	Living Room ceiling surface		
2	Bedroom (R) side ceiling surface		
3	Kitchen ceiling surface		
4	Bedroom Rear (L) side ceiling surface		
5	Bath room ceiling surface		
6	Bedroom FRONT (L) ceiling surface		
7	Kitchen Flooring		
8	Hallway Flooring		
9	Bathroom Flooring		
10	Living Room wall joint compound		
11	Bedroom (L) side wall joint compound		

Total # of Samples \_\_\_\_\_

Relinquished by	Date/Time	Received by	Date/Time

