REPORT OF THE ASBESTOS SURVEY

COF – 6456 Starbrook Drive, Fayetteville NC	**0406-08-9840**

PURPOSE AND SCOPE

An asbestos survey was conducted on August 28, 2020. The purpose of the asbestos inspection of this structure was to locate the asbestos containing building materials (ACBM) to protect human health and the environment. Information in this report should be made available to persons that may come in contact with the asbestos containing materials (ACM) as a result of demolition, repairs, or a change in ownership.

PROJECT DESCRIPTION

A limited survey was performed on the interior and exterior space. No below grade inspection preformed. Not responsible for any ACBM found during demolition.

PROCEDURE

No building plans were available. I was given unlimited access to the Structure. During the walk-through, areas of suspect materials were identified. Representative samples of these materials were collected and analyzed via Polarized Light Microscopy by an NVLAP accredited laboratory.

RESULTS

As you review the data, you will find the following materials were determined to have ASBESTOS:

ACBM – Bathroom Ceiling Surfacing
ACBM – Living Room Ceiling Surfacing
ACBM – Kitchen flooring layer bottom
ACBM – Living room Wall Joint Compound
ACBM – Bedroom wall Joint Compound

If this material is not rendered friable (reduced to powder by hand pressure, also interpreted as chipping, sanding, or grinding), the material does not have to be removed. If, however, this material is made friable, i.e. during demolition, replacement, or renovations, a North Carolina accredited asbestos abatement contractor should perform the removal. Any questions concerning the removal should be directed to the number listed below.

The NESHAP regulation dated Tuesday, November 20, 1990, Part III Environmental Protection Agency, 40CFR Part 61, requires that any building being renovated or demolished be inspected for asbestos containing building materials.

NOTE: If this structure is going to be demolished, or moved an asbestos permit application

and notification for demolition/renovation is required by law to be mailed to the address below 10 working days prior to demolition or asbestos abatement activities.

Health Hazards Control Branch
Occupational and Environmental Epidemiology
Section
NC Department of Environment
Raleigh, NC, 27626-0820
Telephone: (919) 733-0820

An asbestos inspection is a judgement call based on the experience of the inspector. The survey is conducted by sampling substances known to contain asbestos or by sampling materials suspected of containing asbestos.

I the inspector assume no liability for asbestos materials that are not included in an asbestos inspection due to the material being inaccessible, concealed, or not considered suspect ACM. I the inspector assume no liability for the condition of the building materials before or after the inspection.

Sincerely,

JTL 8-28-2020

John T. Leonard
Asbestos Inspector
NC Accreditation # 12254

Bulk Asbestos Analysis

By Polarized Light Microscopy
EPA Method: 600/R-93/116 and 40 CFR, Part 763, Subpart E, App.E

NVLAP TESTING
NVLAP LAB CODE 200644-0

Lab ID # 173190

Customer: JTL Services
3999 Sanderosa Rd.
Fayetteville, NC 28312

Attn: Jay Leonard

Lab Order ID: 71949132
Analysis ID: 71949132_PLM
Date Received: 8/28/2020
Date Reported: 8/28/2020

Project: COF - 0406-08-9840 6456 Starbrook Drive Fayetteville NC 28304

Sample ID / *Lab Sample ID*	Description / *Lab Notes*	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes / Treatment
1 - A	Kitchen Flooring Top	**None Detected**		100% Other	Gray Non Fibrous Heterogeneous
71949132PLM_1	*tile*				Dissolved
1 - B	Kitchen Flooring Top	**None Detected**		100% Other	Tan Non Fibrous Heterogeneous
71949132PLM_9	*mastic*				Dissolved
2	Kitchen Flooring Bottom	**15% Chrysotile**	15% Cellulose	70% Other	Tan Non Fibrous Heterogeneous
71949132PLM_2					Ashed
3 - A	Living Room Flooring	**None Detected**		100% Other	Gray Non Fibrous Heterogeneous
71949132PLM_3	*tile*				Dissolved
3 - B	Living Room Flooring	**None Detected**		100% Other	Yellow Non Fibrous Heterogeneous
71949132PLM_10	*mastic*				Dissolved
4	Sheetrock	**None Detected**	10% Cellulose	90% Other	Gray Non Fibrous Heterogeneous
71949132PLM_4					Crushed
5	Bathroom Ceiling Surfacing	**3% Chrysotile**		97% Other	White Non Fibrous Heterogeneous
71949132PLM_5					Crushed
6	Living Room Ceiling Surfacing	**2% Chrysotile**		98% Other	White Non Fibrous Heterogeneous
71949132PLM_6					Crushed

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommend that analysis of floor tiles, vermiculite, and/or heterogeneous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Analytical uncertainty available upon request. Scientific Analytical Institute participates in the NVLAP Proficiency Testing program. Unless otherwise noted blank sample correction was not performed. Estimated MDL is 0.1%.

Jalen Moore (10)

Analyst

Approved Signatory

P-F-002 r15 1/16/2021

Bulk Asbestos Analysis

By Polarized Light Microscopy
EPA Method: 600/R-93/116 and 40 CFR, Part 763, Subpart E, App.E

NVLAP TESTING
NVLAP LAB CODE 200644-0

INDUSTRIAL HYGIENE ISO/IEC 17025:2005 Accredited Laboratory AIHAACCREDITEDLABS.ORG Lab ID # 173190

Customer: JTL Services
3999 Sanderosa Rd.
Fayetteville, NC 28312

Attn: Jay Leonard

Lab Order ID: 71949132
Analysis ID: 71949132_PLM
Date Received: 8/28/2020
Date Reported: 8/28/2020

Project: COF - 0406-08-9840 6456 Starbrook Drive Fayetteville NC 28304

Sample ID / *Lab Sample ID*	Description / *Lab Notes*	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes / Treatment
7	Bedroom Wall Joint Compound	2% Chrysotile	10% Cellulose	88% Other	White Non Fibrous Heterogeneous
71949132PLM_7	*joint compound only*				Crushed
8	Living Room Wall Joint Compound	< 0.1% Chrysotile	10% Cellulose	90% Other	White Non Fibrous Heterogeneous
71949132PLM_8	*drywall: none detect; joint compnd: 2% chrysotile*				Crushed

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommend that analysis of floor tiles, vermiculite, and/or heterogeneous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Analytical uncertainty available upon request. Scientific Analytical Institute participates in the NVLAP Proficiency Testing program. Unless otherwise noted blank sample correction was not performed. Estimated MDL is 0.1%.

Jalen Moore (10)

Analyst

Approved Signatory

P-F-002 r15 1/16/2021

Scientific Analytical Institute
4604 Dundas Dr. Greensboro, NC 27407
Phone: 336.292.3888 Fax: 336.292.3313
www.sailab.com lab@sailab.com

Lab Use Only
Lab Order ID: 71949132
Client Code: _____

Company Contact Information	
Company: JTL Services LLC	Contact: Jay Leonard
Address: 3999 Sandevosa Road	Phone ☑: 910-237-3519
Fayetteville, NC 28312	Fax ☐:
	Email ☑: moldservicesjtl@aol.com

Billing/Invoice Information	Turn Around Times	
Company: Credit Card on File	90 Min. ☐	48 Hours ☐
Contact: CBF - 0406-08-9840	3 Hours ☐	72 Hours ☐
Address: 6456 STARBROOK DRIVE	6 Hours ☐	96 Hours ☐
Fayetteville NC 28304	12 Hours ☒	120 Hours ☐
	24 Hours ☐	144+Hours ☐

Asbestos Test Types	
PLM EPA 600/R-93/116 (PLM)	☒
Positive stop	☐
PLM Point Count 400 (PT4)	☐
PLM Point Count 1000 (PTM)	☐
PCM NIOSH 7400-A Rules (PCM)	☐
B Rules (PCB) ☐ TWA (PTA)	☐
TEM AHERA (AHE)	☐
TEM Level II (LII)	☐
TEM NIOSH 7402 (TNI)	☐
TEM Bulk Qualitative (TBL)	☐
TEM Bulk Chatfield (TBS)	☐
TEM Bulk Quantitative (TBQ)	☐
TEM Wipe ASTM D6480-05	☐
TEM Microvac ASTM D5755-02	☐
TEM Water EPA 100.2 (TW1)	☐
Other: _____	☐

PO Number:
Project Name/Number:

Sample ID #		Volume/Area	Comments
1	Kitchen Flooring TOP		
2	Kitchen Flooring Bottom		
3	Living Room Flooring		
4	Sheet Rock		
5	Bathroom ceiling surfacing		
6	Living Room ceiling surfacing		
7	Bedroom wall JOINT compound		
8	Living Room wall JOINT compound		

Total # of Samples _____

Relinquished by	Date/Time	Received by	Date/Time
		[signature]	8/28 10:30am

Accepted ☑
Rejected ☐

Page ____ of ____

A-F-017 EXP: 12-1-13

71949132

Client:	JTL services LLC
Contact:	Jay Leonard
Address:	[Enter your street address here]
Phone:	(910) 237-3519
Fax:	[Enter fax here]
Email:	moldservicesitl@aol.com
Project:	COF - 0406-08-9840
Client Notes:	6456 Starbrook Drive Fayetteville NC 28304
P.O. #:	COF - 046-08-9840
Date Submitted:	8/28/2020 0:00
Analysis:	PLM
TurnAroundTime:	12

Instructions:
Use Column "B" for your contact info

To See an Example Click the bottom Example Tab.

Enter samples between "<<" and ">>"
Begin Samples with a "<< "above the first sample and end with a ">>" below the last sample.
Only Enter your data on the first sheet "Sheet1"

Note: Data 1 and Data 2 are optional fields that do not show up on the official report, however they will be included in the electronic data returned to you to facilitate your reintegration of the report data.

Scientific Analytical Institute

4604 Dundas Drive
Greensboro, NC 27407
Phone: 336.292.3888
Fax: 336.292.3313
Email: lab@sailab.com

<<

1	Kitchen Flooring Top	Kitchen Flooring Top	[Enter data of your choosing here]
2	Kitchen Flooring Bottom	Kitchen Flooring Bottom	[Enter data of your choosing here]
3	Living Room Flooring	Living Room Flooring	[Enter data of your choosing here]
4	Sheetrock	Sheetrock	[Enter data of your choosing here]
5	Bathroom Ceiling Surfacing	Bathroom Ceiling Surfacing	[Enter data of your choosing here]
6	Living Room Ceiling Surfacing	Living Room Ceiling Surfacing	[Enter data of your choosing here]
7	Bedroom Wall Joint Compound	Bedroom Wall Joint Compound	[Enter data of your choosing here]
8	Living Room Wall Joint Compound	Living Room Wall Joint Compound	[Enter data of your choosing here]
			[Enter data of your choosing here]
[Enter Sample Numb	[Enter data of your choosing here]	[Enter Sample Description Here]	[Enter data of your choosing here]
[Enter Sample Numb	[Enter data of your choosing here]	[Enter Sample Description Here]	[Enter data of your choosing here]

>>

Relinquished By

Received By

Client:	JTL services LLC
Contact:	Jay Leonard
Address:	[Enter your street address here]
Phone:	(910) 237-3519
Fax:	[Enter fax here]
Email:	moldservicesjtl@aol.com
Project:	COF - 0406-08-9840
Client Notes:	6456 Starbrook Drive Fayetteville NC 28304
P.O. #.	COF - 046-08-9840
Date Submitted:	8/28/2020 0:00
Analysis:	PLM
TurnAroundTime:	12

Instructions:

Use Column "B" for your contact info

To See an Example Click the bottom Example Tab.

Enter samples between "<<" and ">>"
Begin Samples with a "<< "above the first sample and end with a ">>" below the last sample.
Only Enter your data on the first sheet "Sheet1"

Note: Data 1 and Data 2 are optional fields that do not show up on the official report, however they will be included in the electronic data returned to you to facilitate your reintegration of the report data.

Scientific Analytical Institute

4604 Dundas Drive
Greensboro, NC 27407
Phone: 336.292.3888
Fax: 336.292.3313
Email: lab@sailab.com

Sample Number	Data 1	Sample Description	Data 2
<<			
1	Kitchen Flooring Top	Kitchen Flooring Top	[Enter data of your choosing here]
2	Kitchen Flooring Bottom	Kitchen Flooring Bottom	[Enter data of your choosing here]
3	Living Room Flooring	Living Room Flooring	[Enter data of your choosing here]
4	Sheetrock	Sheetrock	[Enter data of your choosing here]
5	Bathroom Ceiling Surfacing	Bathroom Ceiling Surfacing	[Enter data of your choosing here]
6	Living Room Ceiling Surfacing	Living Room Ceiling Surfacing	[Enter data of your choosing here]
7	Bedroom Wall Joint Compound	Bedroom Wall Joint Compound	[Enter data of your choosing here]
8	Living Room Wall Joint Compound	Living Room Wall Joint Compound	[Enter data of your choosing here]
			[Enter data of your choosing here]
[Enter Sample Numbe	[Enter data of your choosing here]	[Enter Sample Description Here]	[Enter data of your choosing here]
[Enter Sample Numbe	[Enter data of your choosing here]	[Enter Sample Description Here]	[Enter data of your choosing here]
>>			

Relinquished By

Received By